



## SPECIFICATIONS

3509 3511

### TRANSPORT

<b>A</b> Transport Height (with boom fully retracted)	7'9" .....	8'10"
Transport Width (with stabilizers up)	5'0" .....	5'0"
<b>B</b> Ground Clearance	11" .....	11"
<b>C</b> Overall Length	7'7" .....	7'9"
Boom Pivot Height	16" .....	16"
Operating Weight w/12" Bucket	1425# .....	1594#

### OPERATIONAL

<b>D</b> Digging Depth Maximum	9'8" .....	11'1"
<b>E</b> Digging Depth (2 Ft.) Flat Bottom	9'7" .....	11'0"
<b>F</b> Digging Depth (8 Ft.) Flat Bottom	8'3" .....	9'11"
<b>G</b> Overall Operating Height - Fully Raised	12'10" .....	14'5"
<b>H</b> Loading Height	6'10" .....	8'0"
<b>J</b> Loading Reach	4'2" .....	5'0"
<b>K</b> Reach From Swing Post	12'9" .....	14'5"
<b>L</b> Bucket Rotation	180° .....	180°
Swing Arc	180° .....	180°
<b>M</b> Straight Wall Digging Depth	7'3" .....	8'2"
Stabilizer Spread Operating Position	7'11" .....	7'11"
Stabilizer Down Below Grade	16" .....	16"
System Relief Valve Setting	2100psi ...	2100psi



503 Gay Street • PO Box 266 • Delhi, Iowa 52223 USA • 319-922-2981 • 800-922-2981 • Fax 319-922-2700 • [www.get-attached.com](http://www.get-attached.com)

A-509-8-00